MYSORE DIVISION.

Dated 28th August 1906.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Mysore Division, up to 29th September 1906 for restoring Upparkanahalli Manchettikere in the Mandya Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1907.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Mysore between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Upparkanahalli Manchettikere;" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; the default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The rates tendered should include royalty for stones, etc., to be paid.

Items of work.	*Per.*	*Quantity.*
Bund—		
Earthwork to bund	C. yd.	18,118
Earthwork to breach	Do	3,591
New stone work	Do	2,618
Old stone work	Do	100
B. M. stone	Each	2
Grade stone including bottom slabs	Do	15
Visa vis stones	Do	15
Date stone	Do	1
Registered number stone	Do	1
Gauge stones	Do	1
Turfing including carting 1½ mile lead	Sq.	495·16
Blasting rock	C. yd.	40
Brick masonry puddle wall	Cft.	1,742
Benching hard rock	Sq. ft.	827
Waste weir —		
Excavation hard gravelly soil including cutting weir channel	C. yd.	7,010
Brick in surki mortar	Cft.	2,466
Burnt stone slabs	Do	224
Plastering with surki mortar	Sq. yd.	5·46
Rough stone work new	C. yd.	811
Sluice Nos. 1 and 2 for the left and right—		
Excavation hard soil	Do	231
Refilling earth in excavated bund including watering and tamping	Do	86
Brick in surki mortar	Cft.	1,692
Burnt stone slabs roughly dressed	Do	125
Cut stone work neatly dressed	Do	21
Plastering with surki mortar	Sq. yd.	8·87
Rough stone revetment, new	C. yd.	15
Baling water	Lump sum	rupees
Teak plug with iron rod lock, etc., complete	Do	
Distribution—		
Opening out irrigation channel all soils	C. yd.	1,613
Mile and zero stones	Each	2
Half furlong or tank grade stones	Do	15
Bed grade stones	Do	16

B. SUBBA RAO,
Executive Engineer.